



Ventoce SPC Flooring Installation Guide

Pre-Installation Essentials

Subfloor Preparation

A smooth and level existing floor is a must. If the surface is not smooth and level, you must do self-leveling.

Moisture Testing

Proper moisture testing is a must. Installation in areas with high moisture, such as kitchens, is not recommended.

Expansion Gaps

Proper expansion gaps around all permanent structures like walls and cabinets are a must.

Floating Floor Integrity

Molding, trim, transition, and finish pieces must not prevent the floor from floating.

Acclimation

Acclimation is normally not necessary but may be required in extreme circumstances or weather conditions.

Installation Guidelines

Product Inspection

Always check flooring planks for defects such as clip chips and color variations under good light conditions.

Clean Grooves

Check that grooves are free of debris.

Pattern Variation

Use planks from multiple boxes during installation to ensure random pattern and color variation.

Climate Control

The flooring must be stored and installed in a climate-controlled area with an average temperature of 55-95°F 13 – 35°C.

Floating System

This product is a floating floor and should not be secured to the subfloor.

Fixed Objects

Do not install fixed objects, such as cabinets, on top of the flooring unless it is fully adhered.

Fastening

Do not fasten trim, molding, or transition pieces directly to the floor.

Prohibited Substrates

This product should not be installed over carpet. Installing over carpet will void the warranty. SPC must be installed on solid surfaces.

Water Resistance & Limitations

Waterproof Status

This product is waterproof but is not a moisture barrier.

Topical Water

The product can withstand topical water and water penetration for up to 16 hours without being damaged.

Subfloor Protection

Water leaking over or around the outer edges of the flooring can damage a wood subfloor and breed mold/mildew growth on subfloors and walls.

Liability

Damage caused by water leakage at the edges is not considered a defect in the flooring.

Summary of Key Installation Requirements

Category	Requirement	Note
Subfloor	Smooth, level, solid surface	Self-leveling required if uneven
Moisture	Low moisture environment	Avoid kitchens and high-moisture areas
Temperature	55-95°F 13 – 35°C	Climate-controlled storage/installation

Expansion Gaps	Mandatory around all permanent structures	Ensure floating floor integrity
Prohibited Substrates	Carpet	Installation over carpet voids warranty

Ventoce - Quality Foundation for Modern Living